

# LEHIGH

## HEIDELBERGCEMENT Group

**TECHNICAL SERVICES**

**SALES & MARKETING**

12667 Alcosta Blvd, Suite 400  
 San Ramon, CA 94583  
 Telephone (925) 244-6562  
 FAX (925) 244-6586



**PLANT LOCATION**

15390 Wonderland Blvd.  
 Redding, CA 96003  
 Telephone (530) 275-1581  
 FAX (530) 275-2525

### CEMENT TEST REPORT

**Cement:** ASTM C150-09, Type II-V, Low Alkali

**Date Shipped:** July 2011

**Report Date:** 8/17/2011

**Destination:** Lot #1246

STANDARD CHEMICAL REQUIREMENTS ASTM C 114	TEST RESULTS	ASTM C 150 SPECIFICATIONS	
		TYPE II	TYPE V
Silicon Dioxide (SiO <sub>2</sub> ), %	19.9	20.0 Min	----
Aluminum Oxide (Al <sub>2</sub> O <sub>3</sub> ), %	4.5	6.0 Max	----
Ferric Oxide (Fe <sub>2</sub> O <sub>3</sub> ), %	4.1	6.0 Max	----
Calcium Oxide (CaO), %	64.0	----	----
Magnesium Oxide (MgO), %	1.7	6.0 Max	6.0 Max
Sulfur Trioxide (SO <sub>3</sub> ), %	2.8	3.0 Max	2.3 Max
Loss on Ignition (LOI), %	2.3	3.0 Max	3.0 Max
Insoluble Residue, %	0.31	0.75 Max	0.75 Max
Alkalies (Na <sub>2</sub> O equivalent), %	0.32	0.60 Max	0.60 Max
Tricalcium Silicate (C <sub>3</sub> S), % <sup>a</sup>	56	----	----
Dicalcium Silicate (C <sub>2</sub> S), % <sup>a</sup>	15	----	----
Tricalcium Aluminate (C <sub>3</sub> A), % <sup>a</sup>	5	8 Max	5 Max
Tetracalcium Aluminoferrite (C <sub>4</sub> AF), % <sup>a</sup>	12	----	----
C3S + 4.75*C3A, %	80	100 Max	----
2 (C <sub>3</sub> A) + C <sub>4</sub> AF, %	22	----	25 Max
PHYSICAL REQUIREMENTS			
(ASTM C 204) Blaine Fineness, m <sup>2</sup> /gm	415	280 Min	280 Min
(ASTM C 430) -325 Mesh, %	94.2	----	----
(ASTM C 1038) Expansion in Water, %	0.005	0.020 Max	0.020 Max
(ASTM C 114) CO <sub>2</sub> , %	2.3	----	----
(ASTM C 114) Limestone, %	4.0	5.0 Max	5.0 Max
(ASTM C 114) CaCO <sub>3</sub> in limestone, %	97	70 Min	70 Min
(ASTM C 191) Time of Setting - Initial (Vicat)	83	45 Min	45 Min
(ASTM C 191) Time of Setting - Final (Vicat)	175	375 Max	375 Max
(ASTM C 451) False Set, %	83	50 Min	50 Min
(ASTM C 185) Air Content, %	7.1	12 Max	12 Max
(ASTM C 151) Autoclave Expansion, %	0.01	0.80 Max	0.80 Max
(ASTM C 187) Normal Consistency, %	25.2	----	----
(ASTM C 109) Compressive Strength, psi (MPa)			
1 Day	2115 (14.6)	----	----
3 Day	3637 (25.1)	1500 (10.3) Min	1160 (8.0) Min
7 Day	4447 (30.6)	2500 (17.2) Min	2180 (15.0) Min
28 Day (previous month)	6228 (42.9)	----	3050 (21.0) Min

This cement meets the requirements of specification:

*Albert J. Cornibe, Jr.*

Albert J. Cornibe  
 Quality Manager

ASTM C150-09 Type II-V, Low alkali  
 Caltrans Section 90-2.01 - Type II-V Modified  
 \* See ASTM 1038 result  
 ASTM C 1157 Portland Cement Type HS  
<sup>a</sup> Adjusted per ASTM C-150-09 Section A1.6  
 AASHTO Practice R18 accredited laboratory